

THIS IS A TWO-SIDED DOCUMENT



**Adirondack
Park Agency**

PO Box 99 · 1133 NYS Route 86
Ray Brook, NY 12977
Tel: (518) 891-4050
www.apa.ny.gov

**APA General
Permit/Order
2024G-1**

Permit #: 2024-0202A

**Certificate for Certain Minor Regulated
Activities in APA Jurisdictional
Freshwater Wetlands**

This certificate under General Permit 2024G-1 is granted to New York State Department of Environmental Conservation, authorizing a minor regulated activity in a freshwater wetland pursuant to the Freshwater Wetlands Act (Environmental Conservation Law, Article 24) and the Adirondack Park Agency Act (Executive Law, Article 27, including Section 809(13)(e)), in an area classified Resource Management by the Official Adirondack Park Land Use and Development Plan as described in the application received by the Agency on July 29, 2026 and as depicted on the attached reduced-scale Project Plans. The project site is in the Town of Diana, Lewis County.

This certificate supersedes Certificate 2024-0202, issued by the Agency on August 15, 2024.

The project shall not be undertaken or continued unless the project authorized herein, including site restoration, is completed within four years of the date of issuance of this certification.

This certificate does not convey any right to trespass upon the lands or interfere with the riparian rights of others in order to undertake the authorized project, nor does it authorize the impairment of any easement, right, title, or interest in real or personal property.

Nothing contained in this certificate shall be construed to satisfy any legal obligations of the permittee to comply with all applicable laws and regulations or to obtain any governmental approval or permit from any entity other than the Agency, whether federal, state, regional, or local.

Failure to comply with this general permit and approved attached Project Plans is a violation and may subject the project sponsor, successors and assigns to civil penalties and other legal proceedings, including modification, suspension or revocation of the permit.

PROJECT SITE

The project site is located on Bryant Bridge Road in the Town of Diana, Lewis County, in an area classified Resource Management on the Adirondack Park Land Use and Development Plan Map. The site is identified as Tax Map Section 047.000, Block 1, Parcel 2.200.

Additional wetlands not described herein or depicted on the Project Plans may be located on or adjacent to the project site.

PROJECT DESCRIPTION AS PROPOSED

The project as conditionally approved herein involves replacement of an existing 12-inch culvert with a 17-inch by 13-inch by 20-foot squash culvert.

The project is shown on the following Project Plans:

- A plan sheet titled "Culvert Replacement 607," received by the Agency on August 1, 2024 (Site Plan); and
- A four-page narrative titled "2) Bryant Bridge Road Culvert Near Oswegatchie Conservation Easement Boundary," received by the Agency on July 29, 2026 (Project Narrative).

A reduced-scale copy of the Site Plan and Page 1 of the Project Narrative for the project is attached to this certificate for easy reference. The original, full-scale maps and plans described in this paragraph are the official plans for the project, with copies available upon request from Adirondack Park Agency headquarters in Ray Brook, New York.

CONDITIONS


1. This permit is binding on the permittee(s) and all contractors undertaking all or a portion of the project authorized herein. Copies of this certificate and Project Plans shall be furnished by the permittee to all contractors prior to undertaking the activities authorized herein.
2. This certificate authorizes minor regulated activities in a freshwater wetland as depicted and described in the Project Plans. Any change to the location, dimensions, materials, or other aspect of the activities authorized herein shall require prior written Agency authorization.
3. Prior to construction, including clearing and grubbing, temporary erosion and sediment control measures shall be installed and maintained as depicted and described in the Project Plans. All silt fence shall be properly installed with the bottom buried at a depth of at least 4 inches. Once the site has been stabilized, silt fence and any other temporary erosion and sediment controls shall be completely removed.
4. All site restoration activities depicted and described in the Project Plans shall be implemented within three days of project completion, and in accordance with the approved implementation schedule.
5. The permittee shall notify the Agency in writing within five business days after the work authorized by this Certificate including any required restoration of temporary wetland impacts has been successfully completed. Written notification shall include color photographs which clearly show the completed work and site restoration and identify the date and location that the photographs were taken.
6. The authorized work shall be scheduled and conducted during drier periods (not during major storm events, spring runoff, and thawing conditions) to avoid and minimize erosion of soils and to prevent silting and muddying of wetlands or surface waterbodies.

7. No mechanized equipment shall be driven in wetlands unless expressly authorized herein. Every effort shall be made to work from upland areas and to minimize disturbances to areas adjacent to wetlands. Only tracked equipment shall be used in wetlands. Vehicular access in wetlands shall be under frozen conditions when possible.
8. Wetland disturbance including grading and grubbing of stumps and roots shall be limited to the area depicted and described on the Project Plans.
9. No waste disposal, material or excavation stockpiling, or dewatering discharge shall occur in or within 100 feet of wetlands unless specifically authorized in the Project Plans.
10. When brought from off-site, all equipment, including but not limited to trucks, excavators, tractors, etc., and hand excavation tools such as shovels, rakes, and picks, to be used on the project site shall be clean and free of soil, mud, or other similar material. If washed on the project site, equipment shall be washed in one location to prevent the distribution of propagules among different wash sites. All construction equipment and vehicles operating in areas that may contain existing invasive species shall be thoroughly cleaned prior to moving to other areas.
11. Any cutting of vegetation along the shorelines of navigable waterbodies shall be in conformance with the Shoreline Restrictions of Section 806 of the Adirondack Park Agency Act. A copy of the Shoreline Restrictions or the Citizen's Guide is available upon request.
12. All tree cutting and/or vegetation removal shall be limited to the area depicted and described on the Project Plans. All cut vegetation shall be immediately removed from the wetland and adjacent area upon completion of the activity.
13. Existing pipe and box culverts shall be replaced at their existing location unless structure re-location or re-alignment is specifically authorized herein. Replacement culverts and any associated scour protection must be installed so that they do not constitute a barrier to upstream movement of fish and other aquatic species.
14. All culverts with closed bottoms (including round culvert pipes) must be appropriately embedded. Round culverts must be installed with at least 20% of the culverts vertical height is embedded below the existing wetland substrate.
15. Native soil material or wetland substrate shall be placed for culvert embedding and spread evenly throughout the bottom of the new culvert where appropriate.
16. New or replacement culverts shall be installed so as to preserve the pre-construction water levels unless specifically authorized herein and shall not inhibit the natural movement of fish or other aquatic species.
17. This certificate amends and supersedes Certificate 2024-0202. The terms and conditions of Certificate 2024-0202 shall no longer apply.

Dated: August 12th, 2024


Ray Brook, New York

ADIRONDACK PARK AGENCY

By: 
John M. Burth
Deputy Director, Regulatory Programs

STATE OF NEW YORK
COUNTY OF ESSEX

On the 12th day of August in the year 2024, before me, the undersigned, a Notary Public in and for said State personally appeared John M. Burth, personally known to me or proved to me on the basis of satisfactory evidence to be the individual whose name is subscribed to the within instrument and acknowledged to me that they executed the same in their capacity, and that by their signature on the instrument, the individual, or the person upon behalf of which the individual acted, executed the instrument.


Notary Public

STEPHANIE PETITH
Notary Public, State of New York
Reg. No. 01PE6279890
Qualified in Essex County
Commission Expires April 15, 2029

NEW YORK
STATE OF
OPPORTUNITY.

**Adirondack
Park Agency**

Date: August 1, 2024



NEW YORK
STATE OF
OPPORTUNITY

**Adirondack
Park Agency**

P2024-0202

The diagram shows a cross-section of a road with a circular culvert. The road surface is shown as a dashed line. The current culvert is a blue circle, and the new culvert is a red circle. The new culvert is 6 inches lower than the current culvert. The slope of the new culvert is 35 degrees. The road surface is labeled 'New Road Surface' and 'Current Road Surface'. The bottom of the new culvert is labeled 'Bottom of New Culvert 6" lower than current culvert'.

Current Road Surface

Bottom of New Culvert
6" lower than current culvert

The diagram illustrates a cross-section of a road. A red rectangular area on the left is labeled "Current Road Surface". To its right, a grey rectangular area is labeled "New Road Surface". A double-headed arrow between the two surfaces is labeled "12\"", indicating the gap between them. The top and bottom edges of the road surface are marked with green circles, representing the road's profile.

New Road Surface

12"

Current Road Surface

A diagram of a rectangular field. A line of trees is shown along the top boundary. An angle of 12° is indicated at the top right corner of the field.

18ft wide roadbed width

14ft wide road tread

Downstream:
OHW 24" wide

Culvert extends
11ft beyond roadbed

Upstream:
Undefined
Channel
Wetland

Cofferdam to be used during construction

- = replacement 35" W x 24" H culvert
- = existing 12" round culvert
- = 4sqft wetland fill
- = rock headwall
- = wetland boundary/edge or roadbed fill

Legend



= replacement 35" W x 24" H culvert

= existing 12" round culvert

 = 4sqft wetland fill

 = rock headwall

 = wetland boundary/edge or roadbed fill
/silt fence location



2) Bryant Bridge Road Culvert near Oswegatchie Conservation Easement Boundary

GPS Location: 44.060472 -75.209515

The existing 12" round x 20ft long culvert was included in JIF J2017-0487 for maintenance (re-covering due to water flowing over the road), and a subsequent field visit occurred. The culvert is partially crushed, and has been frost heaved so that it is damming water on the upslope side of the road. The upstream side of the road has standing water bounded by road fill.

We would like to install a new 17" wide x 13" tall x 20ft long squash culvert that is properly set, and adequately cover the culvert so that water does not flow over the road surface during large rainfall events.

For this project, given the same length culvert, any new fill adjacent to the road would be nominal (17" wide vs 12" wide culvert would equate to less than 1sqft of fill) – and this area does already have fill in it as the roadbed is more or less flush with each end of the culvert, only having eroded during flood events.